(16)

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Name of Work :- Detailed Estimate for:-Annual Maintenance and repairs of street lights in ward no 07 Package Y -07 of Yelahanka Zone.

Budget Head .....

Division No..... Estimate No. ..... For Rs.= 4759000.00

Sl No	SR Page No	Description of Work	Unit	Qty	Rate Per Year Rs. Ps.	Amount
1	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 36/40 W fluorescent tube light street lighting systems.	Each	175	685.45	119953.75
2	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 125 W HPMV light Park lighting systems.	Each	130	756.29	98317.70
3	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents for 250W HPSV street light lighting systems.	Each	2989	1019.41	3047016.49
4	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of street lighting system including replacement of damaged/failed/fused out components like Lamps, Tubes, Chokes, Ignitors, Capacitors, Switches , wires, Holders, Starters ,and switching ON/OFF of street lights at specified timing and Pole numbering, Preparing ward wise, street wise data bank furnishing maintenance reports ,every day etc, complete so as to ensure efficient burning of street lights detailed in tender documents 400 watts HPSV street light/High Mast lighting systems.	Each	58	1118.08	64848.64
5	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 24 watt LED park lighting systems.	Each	40	880.01	35200.40
6	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 65 watt LED street light lighting systems.	Each	700	1147.43	803201.00

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
(ವಿದ್ಯುತ್) ಯಲಹಂಕ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

(5)

7	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 90 watt LED street light lighting systems.	Each	71	1377.66	97813.86
8	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 110/120 watt LED streetlight lighting system	Each	135	1575.5	212692.50
9	AR Vide No SE (Ele) PR/676/2021-22, Dated 7/12/2021	Operation and Maintenance of LED Street lighting system including replacement of damaged/failed/fused out compnents like LED drivers MCPCB surge protective device switches, Wires Holders, Staters observing weather proofing technic confirming to IP 65 standards and switching ON/OFF of Street lights at specified timing and pole numbering. Preparing ward wise Street wise Street light data bank furnishing maintenance reports every day etc.., complete so as to ansure efficient burning of Street lights detailed in Tender documents for 150 watt LED street light /High mast lighting system	Each	1	1871.51	1871.51
10	72/ 13.17.1	Painting of existing Street lighting pole after scraping the old paint and painted with suitable colour enamel/silver paint including copingflooting of the polec) Up to 5 Mtrs Street light pole	Nos	130	550.00	71500.00
11	72/ 13.17.3	Painting of existing Street lighting pole after scraping the old paint and painted with suitable colour enamel/silver paint including copingflooting of the polec) 8 Mtr and above Street light pole	Nos	80	770.00	61600.00
12	26/ 5.14.1	Supply and fixing of 4pole power contactor with NO/NC contacts on existing wood/panel board using necessary bolts, nuts, washers and wiring etc., complete with AC-3 Rating and as per IS-13947.100 to 125Amps	Nos	10	7200	72000.00
13	32/ 5.48	Supplying and fixing Microprocessor Based Astronomical timer Switch with using necessary bolts, nuts and washers.	Each	9	4030.00	36270.00
14	27 5.17.3	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898. 50-63 Amps SP	Each	10	723.00	7230.00
		Total				4729515.85
		GST 12% ITEM 10 to 14	248600.00			29484.00
		Misleniuos				0.15
		Grand Total Rs				4759000.00

Technical Sanction for Rs 47,59,000.00/- (Forty Seven lakhs Fifty Nine Thousand Only)
(Rupees :
is accorded under head P-0300 M&R to Street lights subject
Registered at SE (Ele) No SE/Ele/PR/705/21-22
to conditions contained in enclosed memo
No 34 SE/Ele/TS/134/21-22 Date: 9/12/21
SE (Electrical)
TA

CERTIFICATE

1. The Place was inspected and work is essential
2. The Provision made in the estimate is adequate and are necessary.
3. The Estimate is within the BBMP limit and is legitimate charges on the Corporation Funds.
4. The rates in the Estimate is based on KPWD Electrical SR 2019-20,BESCOM SR 2018-19 and approved rates
5. The Above work is not taken up in any previous Grants.

Administrative Sanction for Rs (47,59,000.00/-) Forty Seven lakhs Fifty Nine Thousand Only
is accorded under Head P-0300
Registered as EE No. 22 Subject
to conditions contained in enclosed memo
No. 22 / 2021 - 22

Executive Engineer

EXECUTIVE ENGINEER (ELEC)
RAJARAJESHWARI DIVISION
BRUHAT BANGALORE MAHANAGARA PALIKE

Asst. Exe Engineer (Elec)
Sub-Division No
Bruhat Bangalore Mahanagara Palike